



KRISH-V GLOBAL INTERIORS

No:1854, 17th main, 30th 'B'Cross, BDA 1stStage,5th Block, HBR layout,Nagawara, Bangalore560043 email:interior@dsgroupworld.in,Contact:+91-8880754754

	Client Name :	Mr/Mrs. ARPITA ARUNDHATI & GAURABH KUMAR PATRA					Date	19-10-2026
	Project Name :	SKY SAMURAI						
	Flat Number :	316						
	Location :							
Sl no	Description	Material Specification	Width	Height	Total Sft	Quantity	Total price	
i	Room type	Kitchen						
1	Kitchen Bottom Cabinet	Carcass -BWR ply with fabric laminate. Sink unit -WPC Board Shutter- HDHMR board with laminate Finish-Acrylic finish (1.5mm) Hardware-Olive Brand	14.50	2.75	39.88	1.00	73768.75	
2	Kitchen Wall Cabinet	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Acrylic finish (1.5mm) Hardware-Olive close	14.50	2.25	32.63	1.00	60356.25	
3	Kitchen Loft Frame and Shutter	Shutter- HDHMR board with laminate Finish- Acrylic finish (1.5mm) Hardware-Olive Brand	14.50	2.50	36.25	1.00	59812.50	
4	Kitchen Wall Cabinet	Kitchen Wall Cabinet Aluminium Glass shutter	2.50	2.50	6.25	1.00	6562.50	
5	Accessosories	Tandem Boxes with accesories-Ebco with Tray			1.00	3.00	19500.00	
6	Accessosories	Cutlery Basket						
7	Accessosories	Plain Basket						
8	Accessosories	Thally Basket						
9	Accessosories	Tandem- Bottle pullout-Ebco			1.00	1.00	7800.00	
10	Accessosories	G profile handle			1.00	5.00	14000.00	
11		kitchen Granite slab (Approx)			1.00	55.00	30250.00	
12		SS-Sink (Approx)			1.00	1.00	10500.00	
13		Dado Tiles (Approx)			1.00	55.00	30250.00	
14	Crockery unit	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Acrylic finish (1.5mm) Hardware-Olive Brand	6.00	7.00	42.00	1.00	73500.00	
15	Crockery unit	Crockery unit Aluminium Glass Shutters	6.00	2.50	15.00	1.00	15750.00	
16	Rolling shutter	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Acrylic finish (1.5mm) Hardware-Olive Brand	2.00	5.00	10.00	1.00	18500.00	
17	Accessosories Rolling shutter	Rolling shutter Mechanism			1.00	1.00	18800.00	
18	Gas Copper piping	Copper piping			1.00	10.00	8800.00	
19	Accessosories	SS-Air Vents			1.00	3.00	1050.00	
ii	Room type	Master Bedroom						
1	Wardrobe	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	7.50	9.50	71.25	1.00	89062.50	
2	Dressing unit	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	2.00	7.00	14.00	1.00	16100.00	
3	Dressing unit	Mirror/ Glass :Modi or Saint Gobain	1.50	6.00	9.00	1.00	3150.00	
4	Study table with Book Shelf	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	4.00	7.00	28.00	1.00	29400.00	
5	MBR King Size Cot Hydraulic Storage	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Ebco/Olive lift up mechanism	6	6.5	39.00	1.00	48750.00	
6	Head Board-Approx	Paneling with Cusion	6	4	24.00	1.00	27600.00	
7	Pooja Unit (DUCO Finish)	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-DUCO Finish Hardware-Olive Brand	3.00	8.00	24.00	1.00	52800.00	
8	Pooja Unit CNC cutting	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	1.50	5.00	7.50	1.00	4875.00	
9	Pooja Unit Shutter	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	3.00	7.00	21.00	1.00	34650.00	
10	MBR Cot wall panelling	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	6.00	8.00	48.00	1.00	31200.00	
11	Accessosories	Wardrobe Sliding Channel With Soft Close			1.00	1.00	14500.00	
12	MBR Accessosories	Wardrobe Dreausers Channel With Soft Close			1.00	5.00	9250.00	

iii	Room type	Kids Bedroom					
1	Wardrobe	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	9.00	7.00	63.00	1.00	78750.00
2	Dressing unit	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	2.00	7.00	14.00	1.00	16100.00
3	Wardrobe	Mirror/ Glass :Modi or Saint Gobain	2.50	6.00	15.00	1.00	5250.00
4	Loft Frame and Shutter	Shutter- HDHMR board with laminate Finish- Laminate finish Hardware-Olive close Brand	11.00	2.50	27.50	1.00	24750.00
5	KBR Queen Size Cot	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Ebco/Olive lift up mechanism	5.5	6	33.00	1.00	41250.00
6	Head Board-Approx	Paneling with Cusion	5.5	3	16.50	1.00	18975.00
7	Accessorios	Wardrobe Sliding Channel With Soft Close			1.00	1.00	17800.00
v	Room type	Living & Dining					
1	TV Unit-Bottom	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	8.00	2.00	16.00	1.00	16800.00
2	TV Unit wall back panelling	TV Unit Wall paneling	8.00	7.00	56.00	1.00	36400.00
3	TV Unit	TV Unit open leadge	10.00	1.00	10.00	1.00	6500.00
4	TV Unit	TV Unit Louvers	2.00	7.00	14.00	1.00	13300.00
5	TV Tall Unit	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	2.00	8.00	16.00	1.00	16800.00
6	TV Tall Unit	Tall unit aluminium profile shutter with glass	2.00	8.00	16.00	1.00	16800.00
7	Living Room Wall Trims beading	Wall Trims beading			1.00	15.00	27750.00
8	Shoe rack with Seating	Carcass -BWR ply with fabric laminate Shutter- HDHMR board with laminate Finish-Laminate finish Hardware-Olive Brand	5.00	2.00	10.00	1.00	10500.00
9	Wash room LED Mirror	Wash room LED Mirror			1.00	2.00	15600.00
10	Complimentary Wash basing bottom cabinet	Carcass -WPC board Shutter- HDHMR board with laminate Finish- Laminate finish Hardware- Olive Brand	2.5	2.5	6.25	2.00	0.00
11	Utility wall Storage Unit	Carcass -WPC board Shutter- HDHMR board with laminate Finish- Laminate finish Hardware- olive Brand	3	2.5	7.50	1.00	7875.00
12	Utility Area	Utility Granite slab (Approx)			1.00	15.00	8250.00
13	Utility Area	SS-Sink (Approx)			1.00	1.00	10500.00
14	Utility Bottom Storage Unit	Carcass -WPC board Shutter- HDHMR board with laminate Finish- Laminate finish Hardware- Olive Brand	3	2.5	7.50	1.00	7875.00
15	Utility Janitor Unit	Carcass -WPC board Shutter- HDHMR board with laminate Finish- Laminate finish Hardware- Olive Brand	1.5	7	10.50	1.00	11025.00
vi	Other	Additional charges					
1	miscellaneous charges	include deep cleaning,transportaion and material unloading			1.00	1.00	12500.00
						Total Cost	1231887.50
						GST 18 %	221739.75
						Grand Total	1453627.25
						AFTER DISCOUNT - 1342000	
Note							
1	All product price is exclusive of tax.18% GST will be extra.						
2	Any changes in handles and other hardwares cost applicable at actuals.						
3	The price will vary based on the design, and the quotation will be updated once the design is finalized						
4	The final bill will be based on the actual measurements taken after the completion of the work						
5	Modifications to electrical and plumbing works will be under the client's scope or will be carried out at an additional cost, depending on site conditions						
6	Validity of quotation will be for 15 days from the date of issue.						
7	Required 60 working days (based on requiremrnt) to complete the Wood work from the date of order confirmation & 50% of payment						
8	Cabinets are made with 18mm (including laminte) plywood and back panel will be 8mm(include laminate)plywood.						
9	Additional charges will be applicable for other finish apart from SF(matt) finish laminate.						
10	The price is subject to change if there are any modifications in material selection						
11	The quoted price includes design charges. In case the client cancels the order, the design charges will still be applicable.						
Payment Terms :				Account name – KRISH V GLOBAL ENTERPRISES PRIVATE LIMITED. Bank Name – Federal Bank Account No - 21980200001889 Account Type - Current Branch - Sadashivanagar IFSC Code – FDRL0002198			
1	RS-50,000/- for PreBooking advance.						
2	50% at initial work confirmation.						
3	40% Before dipatching the material from factory						
4	10% After completion of work.						
	Krish-V			Client :			